BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 36

Name of Work:-Construction of Samudaya Bhavana at 5th phase Yelahanka in Someshwara Ward No 03 Yelahanka New town Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Smt C HEMA GNANESHA (SRI KRISHNA CONSTRUCTIONS)	
				Rate	Rate in Words
1	Dismantling stone slab flooring laid in cement mortar Including stacking of serviceable material and disposal of unserviceable materail to the appropriate disposal area as per direction of Engineer-in-charge	Sqm	299.30	1377.45	One Thousand Three Hundred SeventySeven Paise FourtyFive Only
2	Dismantling of barbed wire fencing/wire mesh fencing including posts, foundation concrete, back filling of pit by manual means including disposal of dismantled material with all lifts and lead, stacking serviceable material and unserviceable material separatelu.	M	26.00	74.32	SeventyFour Paise ThirtyTwo Only
3	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m	Cum	324.88	197.13	One Hundred NinetySeven Paise Thirteen Only
4	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications.	Cum	15.31	2537.92	Two Thousand Five Hundred ThirtySeven Paise NinetyTwo Only
5	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates.	Cum	36.81	5503.95	Five Thousand Five Hundred Three Paise NinetyFive Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6.96	5827.02	Five Thousand Eight Hundred TwentySeven Paise Two Only
7	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1: 6	Cum	52.20	5303.77	Five Thousand Three Hundred Three Paise SeventySeven Only
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	122.54	202.16	Two Hundred Two Paise Sixteen Only
9	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3)	Cum	202.34	73.33	SeventyThree Paise ThirtyThree Only
10	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	T.km	258.99	95.11	NinetyFive Paise Eleven Only
11	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications.M25 Design Mix Using 20 mm nominal size graded crushed coarse	Cum	108.01	6531.81	Six Thousand Five Hundred ThirtyOne Paise EightyOne Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) Ground Floor_ Coloumns upto Beam bottom	Cum	7.51	6743.29	Six Thousand Seven Hundred FourtyThree Paise TwentyNine Only
13	Lintel	Cum	3.22	7356.31	Seven Thousand Three Hundred FiftySix Paise ThirtyOne Only
14	Chejja	Cum	0.82	8888.88	Eight Thousand Eight Hundred EightyEight Paise EightyEight Only
15	Staircase	Cum	2.74	7356.30	Seven Thousand Three Hundred FiftySix Paise Thirty Only

C. Hema Gurl

Signature of the
Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.